

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 9408
Name: Trans Pacific Oil Corporation
Address 1: 100 S Main Ste 200
Address 2: _____
City: Wichita State: KS Zip: 67202 + 3735
Contact Person: Glenna Lowe
Phone: (316) 262-3596
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 051-21647-00-01
Spot Description: _____
E2-NE,SE Sec. 12 Twp. 11 S. R. 19 East West
1,980 Feet from North / South Line of Section
330 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Ellis
Lease Name: Gladys Well #: 3
Date Well Completed: _____
The plugging proposal was approved on: _____ (Date)
by: Case Morris (KCC District Agent's Name)
Plugging Commenced: 3/25/11
Plugging Completed: 3/31/11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8.625	164	135 Sacks Cement
		Production	4.5	3479	150 Sacks Cement

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Bridge at 610'. Ran bit in & hit bridge at 6'. Drilled to 60' & fell through to 600'. Drilled to 810' & fell through. Hit bridge at 1210'. Drilled to 1375', 1600' & 1950'; fell through. Circulated clean. Couldn't get past 1875'. Shot holes at 1675', 1328', 650' & 150'. Ran tubing to 1824' & pumped 25 sacks cement. Pulled to 1328' & pumped 45 sacks cement. Pulled to 650' & pumped 150 sacks cement & 200# hulls. Pulled to 325' & pumped 230 sacks cement & 300# hulls. Pulled tubing out & hooked up to 4 1/2" casing & pumped 50 sacks cement. Pumped 70 sacks cement down 4 1/2" casing and circulated up to 8 5/8".

Plugging Contractor License #: 31925 Name: Quality Well Service, Inc
Address 1: 190 US Hwy 56 Address 2: _____
City: Ellinwood State: KS Zip: 67526 + _____
Phone: (620) 727-3410

Name of Party Responsible for Plugging Fees: Trans Pacific Oil Corporation
State of Kansas County, Sedgwick, ss. Gary Sharp Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Gary Sharp

RECEIVED
APR 28 2011