

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 4058
Name: American Warrior Inc.
Address 1: P.O. Box 399
Address 2: _____
City: Garden City State: Ks. Zip: 67846 + _____
Contact Person: Jody Smith
Phone: (620) 275-2963
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Lansing Depth to Top: 3797 Bottom: 4028 T.D. 4028'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 065-20332 - 00 00
Spot Description: NW-NW-NE
C NW, NW, NE Sec. 33 Twp. 9 S. R. 25 East West
4,950 Feet from North / South Line of Section
2,310 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Graham
Lease Name: Brungardt Well #: A-1
Date Well Completed: 7/23/70
The plugging proposal was approved on: 2/15/11 (Date)
by: Marvin Mills (KCC District Agent's Name)
Plugging Commenced: 4/25/11
Plugging Completed: 4/25/11

Show depth and thickness of all water, oil and gas formations.


Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
<u>Lansing</u>	<u>Oil</u>	<u>Surface</u>	<u>85/8</u>	<u>209'</u>	<u>0</u>
		<u>Production</u>	<u>51/2</u>	<u>4019'</u>	<u>0</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perf 2190' to 2191, 1350' to 1351', 195' to 186', 2spf. Ran tbg to 3750' Swift pumped 175sx 60/40pos, 4% gel with 200# hulls, Pulled tbg to 2200', Pumped 85sx 60/40 pos 4% gel with 200# hulls, Pulled tbg to 1350, Pumped 135sx 60/40 pos 4% gel Cement circulated up annulus. Pulled tbg. Hooked up to 51/2 casing. Pumped 50sx 60/40 poss 4% gel Cement circulated up 85/8 Closed 85/8 in. Pump 30 sx 60/40 pos 4% gel. Pressured to 250# and shut in. Cut pipe off 6' below surface and Back filled.

Plugging Contractor License #: 32382 Name: Swift Services Inc.
Address 1: P.O. Box 466 Address 2: _____
City: Ness City State: Ks Zip: 67560 + 0466
Phone: (785) 798-2300
Name of Party Responsible for Plugging Fees: American Warrior Inc.
State of Kansas County, Finney, ss.
Jody Smith Employee of Operator or Operator on above-described well.
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: 

RECEIVED
APR 27 2011

KCC WICHITA

AP