

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 31191
Name: R & B Oil & Gas, Inc
Address 1: 124 N. Main
Address 2: P.O. Box 195
City: Attica State: KS Zip: 67009 + 9217
Contact Person: Randy Newberry
Phone: (620) 254-7251
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Miss Depth to Top: 4378 Bottom: 4390 T.D. 4390

API No. 15 - 077-20840-00-00
Spot Description: _____
NE NW SW Sec. 21 Twp. 31 S. R. 8 East West
2,310 Feet from North / South Line of Section
990 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Harper
Lease Name: Burgess B Well #: 1
Date Well Completed: 10-12-1982
The plugging proposal was approved on: _____ (Date)
by: Jeff Klock (KCC District Agent's Name)
Plugging Commenced: 7/23/10
Plugging Completed: 7/24/10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8.625	265	225 Sacks Cement
Mississippi	Oil	Production	5.5	4380	100 Sacks Cement

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Cut surface off 4' below ground & checked hole, sand at 4380'. Bailed 5 sacks cement on sand. Ripped casing at 2410' & 2270'; pipe came free at 2270'. Pulled casing up to 1450' & pumped 35 sacks 3%cc & 100# hulls. Pulled to 950' & pumped 35 sacks & 100# hulls. Pulled to 280' & pumped 110 sacks cement to surface. Pulled rest of casing.

RECEIVED
OCT 08 2010

Plugging Contractor License #: 31925 Name: Quality Well Service, Inc.
Address 1: 190 US Highway 56 Address 2: _____
City: Ellinwood State: KS Zip: 67526 + _____
Phone: (620) 727-3410

KCC WICHITA

Name of Party Responsible for Plugging Fees: R & B Oil & Gas, Inc.
State of Kansas County, Harper, ss.
R & B Oil & Gas Inc. Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn and oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Randy Newberry

QUALITY WELL SERVICE, INC.

5022

Home Office 190th US 56 HWY, Ellinwood, KS 67526

Todd's Cell 620-388-5422
Darin's Cell 785-445-2686

Rich's Cell 620-727-3409
Brady's Cell 620-727-6964

Date	7-24-10	Sec.	21	Twp.	31	Range	8	County	HARPER	State	KS	On Location		Finish	
Lease	BURAZZ	Well No.	B-1	Location											
Contractor	QWS							Owner							
Type Job	PTA							To Quality Well Service, Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.							
Hole Size								T.D.							
Csg.	5 1/2							Depth							
Tbg. Size								Charge To							
Tool								R & B OIL & GAS							
Cement Left in Csg.								Street							
Meas Line								Depth							
							City								
							State								
							The above was done to satisfaction and supervision of owner agent or contractor.								
							Cement Amount Ordered								
							180 60/40 4% 1 CC 200 HULLS								
EQUIPMENT															
Pumptrk	6	No.	RILEY			Common			108						
Bulktrk	2	No.	DRIFF			Poz. Mix			72						
Bulktrk		No.	SUN			Gel.			6						
Pickup		No.				Calcium			1						
							Hulls			2					
JOB SERVICES & REMARKS															
Rat Hole							Salt								
Mouse Hole							Flowseal								
Centralizers							Kol-Seal								
Baskets							Mud CLR 48								
DN or Port Collar							CFL-117 or CD110 CAF 38								
1 st Plug 35 SKS 60/40 4%							Sand								
1 CC 400 HULLS @ 1450'							Handling			189					
							Mileage								
2 nd Plug 35 SKS 60/40 4%							FLOAT EQUIPMENT								
102 HULLS @ 950'							Guide Shoe			RECEIVED					
							Centralizer			OCT 08 2010					
3 rd Plug 110 SKS 60/40 4%							Baskets			KCC WICHITA					
@ 380' TO SFC							AFU Inserts								
							Float Shoe								
							Latch Down								
							Pumptrk Charge			PTA					
							Mileage								
													Tax		
													Discount		
													Total Charge		
Signature															