

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 31191
Name: R & B Oil & Gas, Inc.
Address 1: P.O. Box 195
Address 2: _____
City: Attica State: KS Zip: 67009 + _____
Contact Person: Randy Newberry
Phone: (620) 254-7251
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Toronto Depth to Top: 3601 Bottom: 3612 T.D. 3792

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 007-23488-00-00
Spot Description: C NW/4

NW Sec. 13 Twp. 32 S. R. 11 East West
1,320 Feet from North / South Line of Section
1,320 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Barber
Lease Name: Hrencher Well #: B1
Date Well Completed: 12-29-2009
The plugging proposal was approved on: 7/7/10 (Date)
by: Steve Durrant (KCC District Agent's Name)
Plugging Commenced: 7/30/10
Plugging Completed: 8/2/10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8"	254'	175 Sacks Cement
Toronto	Oil	Production	4 1/2"	3786'	175 Sacks Cement

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Cut surface off 4' below ground. Sand at 3560', bailed 4 sacks cement on sand. Ripped casing at 2610' and 2470'; pipe came free. Pulled casing up to 600' and pumped 10 gel & 50 sacks cement. Pulled to 280' & pumped 50 sacks cement. Pulled to 40' & pumped 20 sacks cement.

AR

RECEIVED
OCT 08 2010

Plugging Contractor License #: 31925 Name: Quality Well Service
Address 1: 190 US Highway 56 Address 2: _____
City: Ellinwood State: KS Zip: 67526 + _____
Phone: (620) 727-3410

KCC WICHITA

Name of Party Responsible for Plugging Fees: R & B Oil & Gas, Inc.
State of Kansas County, Harper, ss.
Randy Newberry
(Print Name) Employee of Operator or Operator on above-described well.

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Randy Newberry

QUALITY WELL SERVICE, INC.

5024

Home Office 190th US 56 HWY, Ellinwood, KS 67526

Todd's Cell 620-388-5422
Darin's Cell 785-445-2686

Rich's Cell 620-727-3409
Brady's Cell 620-727-6964

Date	8-2-11	Sec.	13	Twp.	32	Range	11	County	BARBER	State	KS	On Location		Finish	
Lease	H...		Well No.	B1		Location									
Contractor						Owner									
Type Job						To Quality Well Service, Inc.						You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.			
Hole Size						T.D.									
Csg.						Depth						Charge To			
Tbg. Size						Depth						Street			
Tool						Depth						City State			
Cement Left in Csg.						Shoe Joint						The above was done to satisfaction and supervision of owner agent or contractor.			
Meas Line						Displace						Cement Amount Ordered			
EQUIPMENT															
Pumptrk	No.					Common						72			
Bulktrk	No.					Poz. Mix						45			
Bulktrk	No.					Gel.						14			
Pickup	No.					Calcium						1			
JOB SERVICES & REMARKS															
Rat Hole						Hulls						7			
Mouse Hole						Salt									
Centralizers						Flowseal									
Baskets						Kol-Seal									
D/V or Port Collar						Mud CLR 48									
1st plug 125' to 140' @ 100'						CFL-117 or CD110 CAF 38									
2nd plug 140' to 155' @ 100'						Sand									
3rd plug 155' to 170' @ 100'						Handling						137			
100' HULLS @ 600'						Mileage						10			
FLOAT EQUIPMENT												RECEIVED			
2nd plug 170' to 185' @ 100'						Guide Shoe						OCT 08 2010			
100' HULLS @ 270'						Centralizer									
3rd plug 185' to 200' @ 100'						Baskets						KCC WICHITA			
40' TO SFC						AFU Inserts									
						Float Shoe									
						Latch Down									
						4 1/2 Rubber Plug									
						Pumptrk Charge									
						Mileage									
												Tax			
												Discount			
X Signature												Total Charge			