

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 32446
Name: Merit Energy Company
Address 1: 13727 Noel Rd., Suite 500
Address 2: _____
City: Dallas State: TX Zip: 75240 + _____
Contact Person: Lynne Moon / Regulatory Manager
Phone: (972) 628-1569
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Osage Depth to Top: 7423' Bottom: 7498' T.D. 8150'
Spergen Depth to Top: 6600' Bottom: 6989' T.D. _____
Chester Depth to Top: 6180' Bottom: 6432' T.D. _____

API No. 15 - 175-21666 00 00
Spot Description: _____
SE NW SW NE Sec. 10 Twp. 35 S. R. 34 East West
900 3346 Feet from ~~_____~~ / South Line of Section
2150 2163 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Seward
Lease Name: Boles "B" Well #: 3
Date Well Completed: 12/2/98
The plugging proposal was approved on: 10/22/10 (Date)
by: Ken Jehlik (KCC District Agent's Name)
Plugging Commenced: 10/22/10
Plugging Completed: 10/26/10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
<p style="text-align: center;">RECEIVED OCT 29 2010 KCC-WICHITA</p>		Surface	8 5/8"	1614'	NONE
		Production	5 1/2"	7614'	1683'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run tbg set 5 1/2" 10K CIBP & set @ 6130', circulate hole w/ mud & cap w/ 5 sks cement. Cut 5 1/2" at 1683' & POH w/ 5 1/2" csg. TIH w/ tbg @ 1664', mix & spot 80 sks Class "C" cement up to 1359', pull up hole w/ tbg @ 600' & spot 60 sks Class "C" cement up to 378', POH w/ tbg & top out 64' - 4' w/ 15 sks Class "C" cement.

AR

Plugging Contractor License #: 33338 Name: ORR ENTERPRISES, INC.
Address 1: P.O. Box 1706 Address 2: _____
City: Duncan State: Oklahoma Zip: 73534 + 1706
Phone: (580) 467-0258
Name of Party Responsible for Plugging Fees: Merit Energy Company
State of Texas County: Dallas, ss.
Cindy Chavez Employee of Operator or Operator on above-described well.
(Print Name)
being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
Signature: Cynthia Chavez