

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 March 2009 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 6131 Name: Drillers & Producers, Inc. Address 1: P.O. Box 385 Address 2: City: Newton State: Ks Zip: 67114 Contact Person: Bill Hanson Phone: (316) 841-0022 Type of Well: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other SWD Permit #: ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (if needed attach another sheet) mississippi Depth to Top: 2314 Bottom: 2350 T.D. Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D.

API No. 15 - 115-21191 00 00 Spot Description: NE SW NW SW Sec. 5 Twp. 22 S. R. 4 East West 1,728 Feet from North South Line of Section 4,733 Feet from East West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: Marion Lease Name: Lathrop-Hawk A Well #: 3 Date Well Completed: 8-1-85 The plugging proposal was approved on: 7-15-2010 (Date) by: Steve Bond (KCC District Agent's Name) Plugging Commenced: 9-17-10 Plugging Completed: 9-17-10

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Data includes mississippi oil/water surface 8 5/8" 223' 0 and casing 4 1/2" 2349' 992'.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tubing to 2304'-pumped 35 sacks 60/40 poz mix + 4% gel + 4%cc-ran wire line to tag cement at 1944'-shot casing off at 992' and pulled-ran tubing to 276' pumped 142 sacks 60/40 + 4% gel-circulated to surface

RECEIVED OCT 01 2010

KCC WICHITA

Plugging Contractor License #: 5870 Name: Phillips Well Service Inc. Address 1: P.O. Box 1263 Address 2: City: El Dorado State: Ks Zip: 67042 Phone: (316) 321-6650 Name of Party Responsible for Plugging Fees: Drillers & Producers Inc. State of Ks County: Harvey, ss. Bill Hanson (Print Name) Employee of Operator or Operator on above-described well.

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Will Hanson