

15-063-20116-00-00

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 24 1972
04-24-72
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Jack Dunham of Chief Drlg. Co., Inc., has this date requested permission to plug the following described well:

Mr. Dunham guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Company, Incorporated,

Complete Address: 905 Century Plaza, Wichita, Kansas.

Lease Name: Carroll Well No. 1

Location: CNW-SE Sec. 32 Twp. 13 Rge. (E)(W)27

County: Gove Total Depth 4430' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Dunham was instructed to plug the well as follows:

243'--8 5/8" Surface casing, cement circulated with 180 Sx.
Top of Dakota section @ 775'.

Circulate hole with heavy mud. Pull DP to 1000' and displace 110 Cu. Ft. cement thru DP. Pull DP to 275' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

W. L. Richards
Conservation Division Agent