

15-063-20084-00-00

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 22 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Leo Lindenmuth of Chief Drilling Company, Inc., has this date requested permission to plug the following described well:

Mr. Lindenmuth guarantees payment of the plugging fee.

Operator's full Name: Hadel and Gussman,

Complete Address: 514 Union Center, Wichita, Kansas.

Lease Name: Coberly Well No. 1

Location: SE-SE Sec. 15 Twp. 13 Rge. (E)(W) 27

County: Gove Total Depth 4405' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lindenmuth was instructed to plug the well as follows:

244'--8 5/8" Surface casing, cement circulated with 170 Sx.

Circulate hole with heavy mud. Pull DP to 1100' and displace 100 Sx.

cement thru DP. Pull DP to 275' and displace 25 Sx. cement thru DP.

Pull DP, set bridge 40' with 1/2 sack hulls and 10 Sx. cement to bottom

of cellar.

Very truly yours,

N. L. Nichols
Conservation Division Agent