

State of Kansas



15-109-20069-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

11-29-1976

Dear Sir:

Mr. Darrell Steven of Abercrombie Drlg. Inc. has this date requested permission to plug the following described well:

Mr. Darrell Steven guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drlg. Inc. + Mable C. Hoover

Complete Address: 801 Union Center, Wichita, Ks.

Lease Name: Smoky Valley, "B" Well No. #1

Location: NE-SE Sec. 27 Twp. 13 Rge. 33(E) (W) W

County: Logan Total Depth 4270 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Darrell Steven was instructed to plug the well as follows:

- Pump down drill stem.
- 70. sx cem. 50% Pozmix 6% Gel. @ 1100'
- 20 " " " " " " " 250'
- Build Bridge to 40'
- 10. sx cem. 50% Pozmix 6% Gel. 40' to 0'

Very truly yours,

Delbert Ballhazer
Conservation Division Agent