

15-063-20186-00-00

Form CP-3
Rev. 6-4-68

KANSAS

 STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 13 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Abercrombie Drilling, Incorporated,
Complete Address 801 Union Center Building, Wichita, Kansas.
Lease Name Meier Well No. 1
Location CNE-NE Sec. 26 Twp. 13 Rge. (E) (W) 26
County Gove Total Depth 4418'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Above
Address License No.
Operation Completed: Hour 8:15 AM Day 10 Month 6 Year 1973

The above well was plugged as follows:

243'--8 5/8" Surface casing, cement circulated with 170 Sx.
Top of Dakota section @ 700'.

Circulated hole with heavy mud. Pulled DP to 925' and displaced 110 Cu. Ft. cement
thru DP from 925' to 600'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: 
Well Plugging Supervisor

INVOICED

DATE 6/13/73
INV. NO. 9500-W