

15-063-20028-00-20
R

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JUL 15 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Woodman-Iannitti Drilling Company,

Complete Address: 706 Union National Building, Wichita, Kansas.

Lease Name Coberly Well No. 1

Location CSE-SE Sec. 21 Twp. 13 Rge. (E) (W) 27

County Gove Total Depth 11457

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 7:30 PM Day 11 Month 7 Year 1968

The Above well was plugged as follows:

156'--8 5/8" Surface pipe, cement circulated with 135 Sx.
Top of Dakota section @ 875'.

Circulated hole with heavy mud. Pulled DP to 1100' and displaced 100 Sx. cement thru
DP from 1100' to 775'. Pulled DP to 180' and displaced 20 Sx. cement thru DP from
180' to 120'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated,

INVOICED
DATE 7-15-68
INV. NO. 8115-W

Signed: M. L. Nichols
Well Plugging Supervisor