

15-063-20116-00-00

Form CP-3
Rev. 6-4-68

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 24 1972
04-24-72
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Chief Drilling Company, Incorporated,
Complete Address 905 Century Plaza, Wichita, Kansas.
Lease Name Carroll Well No. 1
Location CNW-SE Sec. 32 Twp. 13 Rge. (E) (W) 27
County Gove Total Depth 4430'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Above
Address License No.
Operation Completed: Hour 5:00 PM Day 19 Month 4 Year 1972

The above well was plugged as follows:

243'--8 5/8" Surface casing, cement circulated with 180 Sx.
Top of Dakota section @ 775'.

Circulated hole with heavy mud. Pulled DP to 1000' and displaced 110 Cu. Ft. cement
thru DP from 1000' to 675'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Dickel
Well Plugging Supervisor

DATE 4-27-72
INV. NO. 5609-4