

15-063-20084-00-00

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 22 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Wadel Hussman,

Complete Address 511 Union Center, Wichita, Kansas.

Lease Name Coberly Well No. 1

Location S1-S2 Sec. 15 Twp. 13 Rge. (E) (W) 27

County Gove Total Depth 4405'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Chief Drilling Company, Incorporated,

Address 905 Century Plaza, Wichita, Kans. License No.

Operation Completed: Hour 11:30 AM Day 20 Month 9 Year 1971

The above well was plugged as follows:

2 1/4'--8 5/8" surface casing, cement circulated with 170 Sx.
Top of Dakota section @ 875'.

Circulated hole with heavy mud. Pulled DP to 1100' and displaced 100 Sx. cement thru
DP from 1100' to 775'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *H. L. D. [Signature]*
Well Plugging Supervisor

INVOICED

DATE 9-22-71
INV. NO. 4364-W