

15-063-20083-00-00

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
SEP 13 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Chief Drilling Company, Incorporated,

Complete Address 905 Century Plaza, Wichita, Kansas.

Lease Name R. Leighton Well No. 1

Location CSW-NE Sec. 26 Twp. 13 Rge. (E) (W) 27

County Gove Total Depth 4390'.

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 6:30 PM Day 9 Month 9 Year 1971

The above well was plugged as follows:

254'--8 5/8" Surface casing, cement circulated with 180 Sx.
Top of Dakota section @ 750'.

Circulated hole with heavy mud. Pulled DP to 960' and displaced 100 Sx. cement thru
DP from 960' to 735'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from 275'
to 200'. Pulled DP, set bridge 40' with sack hulls and 10 Sx. cement to bottom
of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 9-14-71

INV. NO. 4325-W