

15-03-20173-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
APR 24 1973
04-24-1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Dane G. Hansen Trust
Complete Address Logan, Kansas
Lease Name Rohr "A" Well No. 1
Location SE SE Sec. 35 Twp. 13 Rge. (E) (W) 30
County Gove Total Depth 3871'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor C & G Drilling
Address Wichita, Kansas License No.
Operation Completed: Hour 1:30 P Day 22 Month 4 Year 1973

The above well was plugged as follows:

RTD 3871' 8 5/8 csg set at 254' cwc 180 sk. Cmt. Mat. 50-50 poz cmt W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 1200' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INDEXED
DATE 4/30/73
INV. NO. 7291-W

Signed: Leo F. Muesel
Well Plugging Supervisor