

15-063-20202-00-00

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION

APR 22 1974  
04-22-1974  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Murfin Drilling Company,  
Complete Address 617 Union Center, Wichita, Kansas.  
Lease Name Weber Well No. B-1  
Location 100' NE of CSW-NW Sec. 35 Twp. 13 Rge. (E) (W) 30  
County Gove Total Depth 4432'  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X  
Other well as hereafter indicated       
Plugging Contractor Above

Address      License No.     

Operation Completed: Hour 4:00 PM Day 14 Month 4 Year 1974

The above well was plugged as follows:

177'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 925'.

Circulated hole with heavy mud. Pulled DP to 1150' and displaced 110 Cu. Ft. cement  
thru DP from 1150' to 825'. Pulled DP to 185' and displaced 30 Cu. Ft. cement thru  
DP from 185' to 110'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. D. Nichols  
Well Plugging Supervisor

INVOICED

DATE 4/23/74  
INV. NO. 8973-W