

15-063-00219-00-00

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 116-39 County: Done

Location: Nw Se Se Sec. 23 Twp. 13 Rge. 30 (E) (W)

Name of Field: _____ Total Depth: 4576

I have this date completed supervision of plugging of:

Lease Name: Steckel Well No. 1

Operator's Full Name: O.A. Sutton Air Prop & Inv.

Complete Address: 407 Ins Bld. Wichita, Kansas

Plugging Contractor: West Supply

Address: Chase, Kans. License No. _____

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 9 am Day 11 Month August Year 1958

The above well was plugged as follows:

T.R.-4576 8 5/8" - 198 5 1/2" - 4210
Send to 4190 and 5 sac cement displaced with dump barrel.
Shot Pipe at 1300' and pulled to 600' chunk mud mixed with
water displaced thru. cut hole, pulled pipe out of hole built
solid rock bridge at 600' and topped with 20 sac cement, chunk
mud to 210' rock bridge and 20 sac cement chunk mud to
40' solid rock bridge and 10 sac cement to bottom of well.

Signed: Herbert P. Leiker
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

PLUGGING
FILE SEC 23 T. 13 R. 30
BOOK PAGE 116 LINE 39

08-24-1958