


R

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Marion County, Sec. 26 Twp. 21 Rge. 4 (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SE SE
Lease Owner E. H. Adair Oil Co.
Lease Name Depler Well No. 4
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 4-19-58 19____
Application for plugging filed 8-8-63 19____
Application for plugging approved 8-8-63 19____
Plugging commenced 8-8-63 19____
Plugging completed 8-8-63 19____
Reason for abandonment of well or producing formation Went Dry

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Cecil Jones
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2458 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Copy of Drillers Log attached hereto.						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set rock bridge at 160 feet. Dumped twenty sacks of cement. Filled hole with mud to thirty feet from surface and put in bridge. Dumped in eight sacks of cement.

STATE CORPORATION COMMISSION

SEP 11 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor E. H. Adair Oil Co.
Address Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Sherrill Compton (employee of owner) or (~~WITNESSETH~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Sherrill Compton
Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of September, 1963

My commission expires 9-15-65 L. Hill Notary Public.



15-115-00559-0000



H. H. Adair Oil Company
1805 East Second Street
Wichita 7, Kansas.

H. H. Adair Oil Company, and
Lee Phillips Oil Company,
No. 4 Depler,
SW 3/4 SW of
Sec. 26, Twp. 21 S., Range 4 East,
Marion County, Kansas.

Comm. April 14, 1958
Comp. April 19, 1958
Contractor:
H. H. Adair - Rig No. 1
3-3/8 @ 160 ft. w/145 cas.
3-1/2 @ 2438 ft. w/ max.

Elevation: 1482 K.S.

Figures indicate bottom of formations

Soil	to	2
Clay		5
Line		33
Clay		41
Broken line		48
Clay		50
Shale		57
Redbeds		64
Shale		68
Broken line		75
(Water from 68 to 73)		
Line		84
Shale		98
Line		160
Line & shale		790
Shale & chert		1100
Shale & line		1738
Line		1739
Shale		1776
Line		1850
Fossiliferous lime		1865

Line	to	3008
Shale		2016
Line		2077
Black shale		2080
Line		2103
Black shale		2188
Line		2130
Shale		2173
Line		2181
Shale		2191
Line & shaly lime		2267
Black shale		2269
Line		2276
Chert		2325
Line		2348
Shale		2444
Dark shale		2458
Dolomite, (show of oil)		2459

RECEIVED
STATE CORPORATION COMMISSION

SEP 11 1960

CONSERVATION DIVISION
Wichita, Kansas

TOTALS

LANSING	1776 (-354)
BASE KANSAS CITY	2130 (-700)
MISSISSIPPI CHERT	2276 (-854)
MISSISSIPPI LIME	2325 (-903)
KENDRICK SHALE	2348 (-926)
CHATTANOOGA SHALE	2444 (-1022)
WICHITA DOLOMITE	2458 (-1036)

WPT No. 1, 2449-59. Open one and one-half hours; weak blow. Recovered 10 feet of oil and 70 feet of oil-cut mud. WPT = 220 lbs. in 20 minutes.

3-1/2 inch casing was cemented at 2458 to test the Huron Dolomite.

K. W. Johnson
K. W. Johnson - Geologist.

Fidelity Union Bank

MADE IN U.S.A.