

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 33036  
Name: Strata Exploration  
Address 1: PO Box 401  
Address 2: \_\_\_\_\_  
City: Fairfield State: Ill Zip: 62837 + 0401  
Contact Person: John R Kinney  
Phone: (618) 842-2610  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_ Depth to Top: 5522 Bottom: 5530 T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: 5538 Bottom: 5542 T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 081-21662-00-00  
Spot Description: \_\_\_\_\_  
W2 NE SE NW Sec. 15 Twp. 29 S. R. 32  East  West  
~~1,000~~ 3661 Feet from  North  South Line of Section  
~~200~~ 3277 Feet from  East  West Line of Section  
Footages Calculated from Nearest Outside Section Corner: for  
 NE  NW  SE  SW 3/28/11  
County: Haskell  
Lease Name: Ricketts Well #: #1  
Date Well Completed: \_\_\_\_\_  
The plugging proposal was approved on: 2/20/11 (Date)  
by: Jack Maciaskey (KCC District Agent's Name)  
Plugging Commenced: 3/28/11  
Plugging Completed: 3/28/11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
St. Louis		surface	8.625	1751	0
		production	5.5	5640	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

RI set CIBP @ 5470 w/25 sxs cement, RU basic pump filler spacer from 4200' up to 1800', perforate @ 1780, RI w/2 3/8 tubing to 1800, hook up to tubing pump 50 sk plug, pulled tubing to 880, hooked back on to tubing, pump h2o to surface TOOH w/tubing, perforate @ 720', tied onto 2x5.5 swedge, pump down 5.5 casing up 8.658 surface w/185 sxs to surface, job complete

Plugging Contractor License #: 34069 Name: Basic Energy Services LP  
Address 1: 500 W Illinois, Ste 800 Address 2: PO Box 10460  
City: Midland State: TX Zip: 79702  
Phone: (432) 620-5528  
Name of Party Responsible for Plugging Fees: Strata Exploration, Inc.  
State of Illinois County, Wayne, ss.  
John R. Kinney  Employee of Operator or  Operator on above-described well,  
(Print Name)  
being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.  
Signature: John R. Kinney