

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 31561
Name: C & K Oil Company
Address 1: P.O. Box 531
Address 2: _____
City: Clafin State: KS Zip: 67525 + 0531
Contact Person: Chris Hoffman
Phone: (620) 786-8744
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 159-22,157 00 60
Spot Description: C E2 NE NE Sec. 22 Twp. 18 S. R. 10 East West
4,620 4622 Feet from North / South Line of Section
330 304 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Rice
Lease Name: Dohrman Well #: 4
Date Well Completed: 07/18/1986
The plugging proposal was approved on: 05/23/2011 (Date)
by: Shane Jones (KCC District Agent's Name)
Plugging Commenced: 05/24/2011
Plugging Completed: 05/27/2011

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8-5/8"	253 ✓	0
		Production	5-1/2"	3253 ✓	1466

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

05/24/11 - Drove to location. Wait 2 hrs on backhoe to plug lead line & dig out cellar. Sand off well 110'. Load hole w/water truck. Move in & rig up. Rig up casing jacks. Let sand fall 1 hr. Ran in w/bailer - tagged sand @ 3150'. Mix up 5 sacks cement. Bail on bottom. Unpack well head. Put on 5-1/2" wiper rubber. Pulled 40k to get slips out of head. Figured stretch in casing @ 5" x 282' per inch for 1410'-1500' - possible recovery. Clean up tools. Shut down.

05/27/11 - Drove to location. Discuss daily safety issues. Hook up loggers. Shot off casing @ 1470'. Pulled 1/2 jt out w/jacks. Pulled 5 jts of 5-1/2" casing up to 1254' for 1st plug. Pumped 35 sacks 60/40 w/4% gel & 3% C.C. w/100# cotton seed hulls. Pulled 8 jts up to 908' for 2nd plug. Wait 1-1/2 hr for cement to set up. Run in w/bailer. Tagged @ 1125'. Pump 2nd plug w/35 sacks 60/40 w/100# cotton seed hulls. Pulled 14 jts up to 302' for 3rd plug. Pumped 35 sacks 60/40 cement. Pulled 7 jts out. Break out head. Top off cement. Clean up jacks. Rig down jacks. Rig down. **1466' total 5-1/2" pipe recovered.

Plugging Contractor License #: 6901 Name: D.S. & W. Well Servicing, Inc.
Address 1: 1822 24th Street Address 2: _____
City: Great Bend State: Kansas Zip: 67530 + _____
Phone: (620) 793-5838
Name of Party Responsible for Plugging Fees: C & K Oil Company
State of Kansas County, Barton, ss.
Tim Dickson Employee of Operator or Operator on above-described well.
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Tim Dickson

RECEIVED

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

JUN 03 2011

KCC WICHITA