

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-051 05938-0000

LEASE NAME Baumer "B"

WELL NUMBER #31

1980' Ft. from S Section Line

2310' Ft. from ^W Section Line

SEC. 27 TWP. 11S RGE. 17W ^{XX} or (W)

COUNTY Ellis

Date Well Completed 02-03-41

Plugging Commenced 10-21-87

Plugging Completed 10-26-87

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Phillips Petroleum Company

ADDRESS Rt. #3, Box 20-A, Great Bend, KS 67530

PHONE# (316) 793-8421 OPERATORS LICENSE NO. 5229

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-07-87 (date)

by Shari Feist (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Arbuckle Depth to Top 3564' Bottom 3574' T.D. 3574'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. MIRU Allied Cmtg truck, pmp dn backside. Fluid came back up csg. Hook on csg, pmpd dn 3 sx hulls mixed w/110 sx cmt, till cmt came out backside valve. Shut back-sid in, press csg to 500 PSI, SI press-300 PSI. Wtd on cmt. Capped csg w/plate. Backfill cellar.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Company License No. RECEIVED

Address Plainville, KS 67663 STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Barton, ss. 12-08-87
DEC 8 1987

S. J. Reynolds (Employee of Operator) CURRY, O. D. DAVISON of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) S. J. Reynolds

(Address) Rt. #3, Box 20-A, Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 7th day of December, 19 87


Patricia L. Prosser
 Notary Public



Commission Expires: 07-30-90

15-051-09938-0000
F 2.094

Well No. **31 Baumer** Farm Sec. **27** Twp. **118** Range **17W**
 Drilling Contractor **Helmerich & Payne, Inc.** Ellis County **Kan.** State **640** Acres
 Drilling Commenced **January 9, 1941**
 Drilling Completed **February 3, 1941**
 Commenced Production **February 3, 1941**
 Natural Production First 24 Hours **Pot. 110,929** bbls.
 Natural Production Second 24 hours **Pro. 49.8** bbls.



T. D. 3574

RECORD OF PAY SAND

Silicious Lime	3564	3568	Show oil 0 3568		
" "	3568	3559	Hole filled 700' in 45 min.	Cent. E/8 NE SW Feet from N. line	Feet from E. line
" "	3569	3573	Hole filled 1300' in 2 1/2 hrs. 1930	Feet from S. line	2310 Feet from W. line
" "	3575	3574	Hole filled 2100' in 3 1/2 hrs.	Fresh water from	to
				Salt water from	to
				Salt water from	to
				Salt water from	to
				Wooden Conductor-Size	Feet
DRIVE PIPING, CASING, TUBING AND RODS					
	Size	Wt. per Ft.	Put In	Pulled Out	
	13"	50 LW	34'5"	No recovery	
	8 5/8	28 LW	1511'	" "	
	5 1/2	17 LW	3564		
	13" SH LW	cemented w/30 sax			
	8 5/8 SH LW	" w/380 sax			
	5 1/2 SH LW	" w/350 sax			

TORPEDO RECORD

Date of Shot	Qts.	Top Shot	Box Shot	Remarks
8-2-41	acidized w/1000 gal			hole filled up
				2100' before acidizing in 3 hrs. - after acid
	Echometer Pot.	110,929		bbls.

Packer set at Size and Kind
 Packer set at Size and Kind
 Packer set at Size and Kind
 Water well Feet at \$ Contractor furnished per foot
 Price of Contract \$ 2.75 per foot Fuel & wtr. & drilling in front.
 Approved
 OCT 7 1941 Superintendent
 STATE OF KANSAS
 Wichita, Kansas

NOTE: All measurements taken from top of Rotary Bushing which was 3'6" above casing head.