

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas, 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-051-05042-0000

LEASE NAME Baumer

WELL NUMBER B-34

1980 Ft. from S Section Line  
ANB KCC

1650 Ft. from E Section Line

SEC. 27 TWP. 11 SRGE. 17 WXDEN or (W)

COUNTY Ellis

Date Well Completed 11-24-41

Plugging Commenced 12-28-90

Plugging Completed 1-24-91

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Phillips Petroleum Company

ADDRESS Rt #3 Box 20-A Great Bend, KS. 67530

PHONE# (310) 793-8421 OPERATORS LICENSE NO. 5229

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by \_\_\_\_\_ (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3586'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	1326'	none
				4 1/2"	3565'	1121ft.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.  
Sanded bottom to 3515' dumped 4 sacks cement. Shot pipe @1931', 1323', 1121'. Down 8 5/8" casing mixed 25 sacks cement followed with 500# hulls in 275 sacks 60/40 8% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Phillips Petroleum Company

STATE OF Kansas COUNTY OF Rice, ss. FEB 6 1991 02-06-91

R. Darrell Kelso (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 4 day of Feb., 19 91

[Signature]  
 Notary Public

My Commission Expires:





52	75	Surface rock
75	125	Sticky shale
125	200	Shale and shells
200	729	Sand and shale
729	800	Shale and shells
800	975	Sand
975	1065	Shale and shells
1065	1200	Red bed and iron
1200	1332	Shale and shells
1332	1332	Anhydrite
1332	1475	Shale and shells
1475	1630	Sticky shale and shells
1630	1630	Shale and shells
1630	2160	Line and shale
2160	2245	Shale and shells
2245	2275	Line and brown shale
2275	2305	Line and shale
2305	2730	Shale and shells
2730	2760	Line and shale streaks
2760	2830	Shale and shells
2830	3012	Line and shale
3012	3045	Line
3045	3090	Line hard
3090	3114	Line
3114	3119	Shale
3119	3160	Line K.C.
3160	3215	Line hard
3215	3260	Line
3260	3410	Line K. C.
3410	3542	Line
3542	3550	Line K.C.
3550	3574	Line - Top Silicious 3544'
3574	3579	Broken Line
3579	3584	Line
3584		Total Depth

15-051-05042-0000

Tops as noted from samples by  
Walt Henderson, Geologist

3260	Top Dodge
3275	Top Lansing K. C.
3280	Very small show oil
3280	3283 Galitic - good saturation
3410	3415 Very small show oil
3424	3430 Very small show oil
3512	3520 Very small show oil
3535	3538 Slight oil stain
3554	Top Simpson
3544	Top Arbuckle