


WELL PLUGGING RECORD
OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

15:051:00913:00-00

NORTH



Locate well correctly on above
Section Plat

Ellis County, Sec. 27, Twp. 13S, Rge. 20W (E) (W)
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines CE 1/2 NW 1/4 SE 1/4
Lease Owner: Darby Petroleum Corporation
Lease Name: Giebler Well No. 1
Office Address: 1015 Philtower Bldg., Tulsa, Okla.
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole.
Date, well completed: August 25, 1941. 193
Application for plugging filed: August 29, 1941. 193
Application for plugging approved: August 30, 1941. 193
Plugging Commenced: September 16, 1941. 193
Plugging Completed: September 20, 1941. 193
Reason for abandonment of well or producing formation: Dry Hole.

If a producing well is abandoned, date of last production: 193
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well: C. T. Alexander
Producing formation: Dry Hole Depth to top: Bottom: Total Depth of Well: 3899 Feet.
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Line	Dry	3833	3899	8 5/8"	1526' 7"	NONE
					3848' 3"	3523' 5"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with mud 3899' to 3835', bridge and cement to 3815' and mud to 1520'. Permanent bridge placed at 1520' and cement to 1500', mud to 30', cement to 8' and mud to surface.

8 5/8" 32# 8thd SS Casing cemented to top with 500 sacks of cement.
5 1/2" 15# 8thd SS Casing cemented with 50 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to: Darby Petroleum Corporation,
Address: 1015 Philtower Building,
Tulsa, Oklahoma.

STATE OF OKLAHOMA, COUNTY OF TULSA, ss.
W. H. Barclay (employee of owner) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. H. Barclay

1015 Philtower Bldg., Tulsa, Oklahoma.
(Address)

SUBSCRIBED AND SWORN to before me this 26th day of September, 1941.

My commission expires March 1, 1942.

17-6058 10-88-5M

Notary Public.

(SEE OTHER SIDE FOR FORMATION RECORD)

FORMATION RECORD

	<u>FROM</u>	<u>TO</u>	
Shale & shells	0	795	
Shale, sand & iron	795	985	
Sand	985	1215	
Shale & shells	1215	1501	
Gyp	1501	1506	
Anhydrite	1506	1544	
Shale & shells	1544	1990	
Salt	1990	2065	
Shale & shells	2065	2190	
Shale & lime	2190	2510	
Lime, broken	2510	2605	
Shale & broken lime	2605	2750	
Lime & shale	2750	3170	
Lime	3170	3899	T.D.

Hole full of Water at 3899' T.D.