

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Leben Oil Corp.

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

PHONE# (918) 494-0000 OPERATORS' LICENSE NO. 6566

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well).

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #4, Hays, KS

Is ACO-1 filed? on old form if not, is well log attached? -

Producing Formation Arbuckle Depth to Top 3826 Bottom 3843 T.D. 3843

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil	3826	43	8-5/8	200	-0-
				5-1/2	3804	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Junk (tbg.) was left in hole to 3630'. Perf'd. @ 1525' and 780'. Spotted 325 sxs cmt 3550' to surface. (JOB COMPLETE)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kaiser-Francis Oil Company License No. 6568

Address P. O. Box 21468, Tulsa, OK 74121-1468

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Van Valkenburg  
 (Address) P. O. Box 21468, Tulsa, OK 74121

SUBSCRIBED AND SWORN TO before me this 2nd day of December, 19 87

Deborah L. Harrell  
 Notary Public

My Commission Expires: 12-6-89

# DREILING OIL, INC

Victoria, Kansas 07671

Kaiser Francis Oil Co.		<b>WELL LOG</b>	15-051-22594-00-00	
<b>Company</b>	P. O. Box 791 Hays, KS 67601 % Ray Youtsey		<b>Sec.</b> 27	<b>Twp.</b> 13 <b>Rng.</b> 20
<b>Farm</b>	Giebler No. 2		<b>Location</b>	C SE NW SE
<b>Total Depth</b>	3807'		<b>County</b>	Ellis
<b>Comm.</b>	9-10-81	<b>Comp.</b>	9-16-81	<b>Elevation:</b> 2205' <b>K. B.</b>
<b>Contractor</b>	Dreiling Oil, Inc. Rt. #1 Victoria, KS 67671			2202' <b>D. F.</b>
				2200' <b>G. B.</b>

<b>Casing Record</b>	<b>Cement Record</b>	<b>Production:</b>
206' - 8 5/8"	150 sacks cement	
3804' - 5 1/2"	200 sacks cement	

**Figures Indicate Bottom of Formations**


0'	70'	Top Soil & Post Rock
70'	213'	Shale
213'	274'	Shale
274'	1277'	Shale & Sand
1277'	1514'	Shale & Red Bed
1514'	1555'	Anhy.
1555'	1782'	Shale
1782'	2226'	Shale & Lime
2226'	2437'	Shale & Lime
2437'	2757'	Lime & Shale
2757'	3003'	Shale & Lime
3003'	3192'	Shale
3192'	3344'	Lime
3344'	3476'	Lime
3476'	3484'	Lime
3484'	3550'	Lime
3550'	3636'	Lime
3636'	3722'	Lime
3722'	3798'	Lime
3798'	3807'	Lime
3807'	T.D.	

STATE OF KANSAS)  
 )ss  
 COUNTY OF ELLIS)

I, Patty Dreiling, of Dreiling Oil, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from the Giebler #2.

*Patty Dreiling*  
 Patty Dreiling

Subscribed and sworn to before me this 21st day of September, 1981.



*Cecilia Basgall*  
 Cecilia Basgall Notary Public

My commission expires: January 19, 1985