

6050157

API NUMBER 15-063 20 862-00-0R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

Q 86-New, SEC. 10, T. 13 S. R. 270 W/O

3300 feet from SE section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5313

Lease Name Terzick Well # 91

Operator: F & M Oil Co.

County Gove 144.76

Name & Address 422 Union Center

Well Total Depth 4454 feet

Wichita Kans 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 386 ✓

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor B & B Drilling License Number 5100

Address 501 Union Center Wichita Kans 67202 Right 13

Company to plug at: Hour: 3 PM Day: 21 Month: Dec Year: 19 84

Plugging proposal received from John Armbruster

(company name) B & B Drilling Co. (phone) _____

were: Order 195 sac 50/50 / Pos mix 6% Gel - 3% CC - 1 sac flo cel - 1 sac shells + 8 5/8 Plug

Get Pitts emulcate hole with heavy mud - with heavy mud between all plugs and no fluid loss.

1st Plug @ 2130' end 25 sac 3rd Plug at 420' end 40 sac

2nd Plug @ 1120' end 110 sac w/ 1 sac flo cel. 4th Plug @ 40' 8 5/8 plug 1 sac shells and 10 sac

10 sac rat hole Plugging Proposal Received by _____ (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6:00 PM Day: 21 Month: Dec Year: 19 84

ACTUAL PLUGGING REPORT

1st Plug @ 2130' w/ 25 sac

2nd Plug @ 1120' w/ 110 sac

3rd Plug @ 420' w/ 40 sac

4th Plug @ 40' solid bridge with 8 5/8 Plug 1 sac shells 10 sac cement

10 sac in Rat Hole - Cemented by Allied

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED did (not) observe this plugging.

DATE 1-14-85

INV. NO. 6412

Signed Gilbert P. Leiker
(TECHNICIAN)

Dec 28 84