

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-21073-00-00
Spot: NESWNWSE Sec/Twnshp/Rge: 27-13S-26W
1680 feet from S Section Line, 2290 feet from E Section Line
Lease/Unit Name: TURNER R Well Number: 1
County: GOVE Total Vertical Depth: 4124 feet

Operator License No.: 31668
Operator Name: H & H INVESTMENTS
Address: PO BOX 1433
HAYS, KS 67601

9/25

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 260
Production: Size 4.5 feet: 4124 **134.03**
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 9/25/00 12:00:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RON Company: H&H INVESTMENTS Phone: (785) 625-6636

Proposed Plugging Method: Order sand and common cement.
Order 8 yards Redi-Mix.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/25/2000 5:00 PM KCC Agent: CARL GOODROW

Actual Plugging Report:
8 5/8" set at 260' w/180 sxs cwc. 4 1/2" set at 4124' w/125 sxs.
Prod perf 3936' - 3942'. PBTD 4112'. Sanded bottom back to 3895' w/ 4 sxs common cement on sand with bailer. Shots at 2500' and 1800'.
Recovered 1238' of 4 1/2" - loaded hole with 8 yards Redi-Mix to surface. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION
OCT 11 2000
10-11-00
CONSERVATION DIVISION
Wichita, Kansas

Remarks: ALLIED CEMENT COMPANY
Plugged through:

District: 04

Signed Carl Goodrow
(TECHNICIAN)

10-

INVOICED
DATE 10/16/00
INV. NO. 200.1060828

Form CP-2/3

OCT 03 2000

MURFIN DRILLING COMPANY

250 N. WATER, #300

WICHITA, KS. 67202

CONTR COMPANY TOOLS

GEOLOG BOB ANTLE

ELV 2413 KB SPD 10/29/86 CARD ISSUED 1/29/87
2408 GL DRLG COMP 11/4/86

#1 R. TURNER

CTY GOVE

FIELD WC(1 SE OF LAHMAN)

IP P 70 BOPD, NW &


2 MCFGPD

LKC 3936-3942

27-13-26W

1680' FSL&

2290' FEL, SE/4



LOG	Tops	Depth/Datum
ANH	1915+	498
B/ANH	1958+	455
WAB	2974-	561
TOP	3433-	1020
HEEB	3663-	1250
TOR	3684-	1271
LANS	3703-	1290
PAW	4123-	1710
FT SC	4186-	1773
CHER	4215-	1802
MISS	4291-	1878
PBTD	4112-	1699
RTD	4328-	1915

API 15-063-21,073

8 5/8 " 260 / 180 SX, 4 1/2 " 4124 / 125 SX
NO CORES

DST (1) 3917-3969 (LKC) / 30-50-45-65, REC 72' DM, W / FEW
OIL SPKS, 62' HOCM, 434' HMC0, 186' CLEAN GSY OIL, SIP
1218-1187#, FP 190-296 / 328-328#, HP 2094-1989#
MICT - CO, PF (LKC) 3936-3942, W / 2 SPF, AC 250 GAL (15%
MCA), SWB DWN, GSO, SET 2 3/8 " TBG AT 3926, POP, P 70
BOPD, NW & 2 MCFGPD (GR 37%), 12/6/86

COPYRIGHT 1985
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS