

3-25
4-032213

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-063-20,354-00-00

SW NW NW /4 SEC. 15, 13, 30 W
4290 feet from S section line
4950 feet from E section line

Operator license# 4058

Lease: Wilson Well # 1

Operator: American Warrior, Inc.

County: Gove 147.06

Address: P.O. Box 399
Garden City, Kansas 67846

Well total depth 4525 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 251 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Mike's Testing & Salvage License# 31529

Address: Chase, Kansas 67524

Company to plug at: Hour: P.M. Day: 25 Month: March Year: 1997

Plugging proposal received from: James Ray

Company: Mike's Testing & Salvage Phone:

Were: Order 225 sxs 60/40 pozmix - 10% gel - 500# hulls.
Halliburton Services.
Order sand & common cement.

RECEIVED
KANSAS CORP COM
1997 MAR 27 A 11:42
03-27-1997

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 2:00 P.M., Day: 25 Month: March Year: 1997

Actual plugging report: 8 5/8" set at 251' w/200 sxs. 4 1/2" set at 4500' w/250 sxs.
Prod. Perfs at 3974' - 4389'. PBTD 4450'. Sanded bottom back to 3925' w/4 sxs common cement
on sand with bailer. Shots at 2150' - 1300' and 1000'. Recovered 1000' of 4 1/2" casing.
Plug through casing with 100 sxs to 2200'. Pulled casing to 300' circulated with 40 sxs
cement. Pulled casing. Topped off with 20 sxs cement. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: GL

I did [X] / did not [] observe the plugging.

Carl Goodrow
(agent)

INVOICED
DATE 3-27-97
INV. NO. 47828