

9-9

4-061114

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-063-21,509-00-00
165' N. of
S2 NE SW /4 SEC. 15, 13 S, 30 W
1815 feet from S section line
3300 feet from E section line

Operator license# 5316

Lease: Sam Brookover Well # 1

Operator: Falcon Exploration, Inc.

County: Gove 149.92

Address: P.O. Box 75067
Wichita, Kansas 67275

Well total depth 4613 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 348 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Discovery Drilling License# 5929

Address: Hays, Kansas 67601

Company to plug at: Hour: 12:15 A.M. Day: 9 Month: September Year: 1997

Plugging proposal received from: Tom Alm

Company: Discovery Drilling Phone: -

Were: Order 200 sxs 60/40 posmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 2:00 A.M. Day: 9 Month: September Year: 1997

Actual plugging report:

- 1st. Plug at 2350' w/25 sxs. - Anhydrite 2320' - 2354'.
- 2nd. Plug at 1440' w/100 sxs. - Dakota 1132' - 1432'.
- 3rd. Plug at 400' w/40 sxs. - Surface pipe to 348'.
- 4th. Plug at 40' w/10 sxs.

Rathole with 15 sxs.

Mousehole with 10 sxs.

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 17 1997
09-17-1997
CONSERVATION DIVISION
WICHITA, KS

Remarks: Allied Cementing.

Condition of casing (in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug (in place): YES, CALC, NO X Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: 2882 GL

I did [] / did not [X] observe the plugging.

[Signature]
DH (agent)

Form CP-2/3

INVOICED

DATE 9-23-97

INV. NO. 49080

9-9