

6 040311

API NUMBER 15-063-20,868-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW SW SW, SEC. 10, T 13 S, R 31 W E
330 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name Stevenson K Well # 1

Operator: Donald C. Slawson

County Gove 151.94

Name & Address 200 Douglas Bldg.

Well Total Depth 4675 feet

Wichita, Ks.

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 309 1/2 210

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XX

Other well as hereinafter indicated _____

Plugging Contractor Slawson Drilling Co. License Number 5657

Address Wichita, Ks.

Company to plug at: Hour: AM Day: 11 Month: January Year: 19 85

Plugging proposal received from Jim Loftus

(company name) Slawson (phone) _____

were: Order 200 sks 50/50 pozmix 6% gel 3% cal. cl., 2 sks hulls and 8 5/8" plug
Spot with drill pipe with no less than 36 vis. mud between all plugs, with good
circulation and no fluid loss.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None XX

Operations Completed: Hour: 11 AM Day: 11 Month: January Year: 19 85

ACTUAL PLUGGING REPORT

1st plug @ 2450 w/40 sks

2nd plug @ 1500 w/100 sks w/2 sks hulls

3rd plug @ 320 w/40 sks

4th plug @ 40 w/10 sks solid bridge

10 sks in Rat Hole

Remarks: Cemented by Halliburton

(If additional description is necessary, use BACK of this form.)

INDICED (if did not) observe this plugging.

DATE 1-29-85

INV. NO. 6739

Signed Dennis L. Hamel (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION

JAN 17 1985 01-17-85 CONSERVATION DIVISION Wichita, Kansas