

10-29

6-050126\_

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-109-20,558-00-00

S2 S2 NE /4 SEC. 9, 13 S, 33 W  
2970 feet from S section line  
1320 feet from E section line

Operator license# 30407 Lease Garvey well # 1

Operator: Black Petroleum Co. County Logan

Address: P. O. Box 12922 Well total depth 4664 feet <sup>151.58</sup>  
Wichita, Kansas 67277-2922 Conductor Pipe:        inch @        feet  
Surface pipe 8 5/8 Inch @ 274 feet

Aband. oil well       , Gas well       , Input well       , SWD       , D & A X

Plugging contractor: White & Ellis License# 5240

Address: Wichita, Kansas

Company to plug at: Hour: PM Day: 29 Month: October Year: 1993

Plugging proposal received from: Judy

Company: White & Ellis phone: 316-263-1102

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 2480 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1410 feet " 100 " Mousehole:        sacks

3rd plug @ 325 feet " 40 "

4th plug @ 40 feet " wiper plug & 10sx

Plugging Proposal Received by: Bruce D. Basye

Plugging operations attended by agent? All[        ], Part[        ], None[ X ]

Completed: Hour: 7:45 PM, Day: 29, Month: October, Year: 1993

Actual plugging report: Hole reported plugged as above.

Order 190 sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 07 1993  
12-01-1993  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Elevation: 3018 GL, Anhydrite depth: 2469 - 2490 feet

Did not penetrate Arbuckle, cemented by Allied

I did[        ] / did not[ X ] observe the plugging.

*Bruce D. Basye*

Bruce D. Basye Geologist  
(agent)

Form CP-2/3

**INVOICED**

DATE 12-3-93

INV. NO. 39321

10-29 DEC 30 1993