

4-060623

11-26

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-109-20,574-00-00  
60'E.of  
SW NW NW /4 SEC. 18 , 13 S, 33 W  
4290 feet from S section line  
4890 feet from E section line

Operator license# 3966 Lease Smothermon well # 1

Operator: Wanker Oil County Logan

Address: R.R. 2 - Box 14 Well total depth 4650 feet  
WaKeeney, Kansas 67672 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 206 feet

157.13

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Emphasis Oil Operations License# 8241

Address: Russell, Kansas 67665

Company to plug at: Hour: 2:00A.M. Day: 26 Month: November Year: 94

Plugging proposal received from: Jack Fox

Company: Emphasis Oil Operations Phone: 913-483-3518

Were: Order 200 sxs. 60/40 posmix - 6% gel with 1/4# flocele per. sx.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 2:00A.M., Day: 26, Month: November, Year: 94

Actual plugging report:

1st. plug at 2425' w/25 sxs. - Anhydrite 2411' - 2434'.

2nd. plug at 1375' w/100 sxs. - Dakota 1070' - 1370'.

3rd. plug at 260' w/40 sxs. - Surface pipe to 206'.

4th. plug at 40' w/10 sxs.

Rathole with 15 sxs.

Mousehole with 10 sxs.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 12 1994

12-12-1994

CONSERVATION DIVISION

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD  BAD  Anhy. plug: YES  NO

Bottom plug(in place): YES , CALC , NO  Dakota plug: YES , NO

Plugged through TUBING , CASING . Elevation: 2970 GL

I did  did not  observe the plugging.

(agent)

Form CP-2/3

**INVOICED**  
DATE 12-12-94  
INV. NO. 41904