

6- 100509

TO:

API number: 15-109-20,600-00-00

11-22

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

W2 NW SW /4 SEC. 10, 13 S, 33 W  
1980 feet from S section line  
4950 feet from E section line

Operator license# 6113

Lease Kuhlman well # 1-10

Operator: Landmark Oil Expl., Inc &  
Vess Oil Corporation  
Address: 250 North Water  
Suite 308  
Wichita, KS 67202

County Logan

150.74

Well total depth 4638 feet  
Conductor Pipe: \_\_\_ inch @ \_\_\_ feet  
Surface pipe 8 5/8 Inch @ 264 feet

Aband. oil well \_\_\_\_, Gas well \_\_\_\_, Input well \_\_\_\_, SWD \_\_\_\_, D & A X

Plugging contractor: L.D. Drilling, Inc. License# 06039

Address: Greear Bend, Kansas 67530

Company to plug at: Hour: ?? Day: \_\_\_\_\_ Month: \_\_\_\_\_ Year: \_\_\_\_\_

Plugging proposal received from: Greg Davidson

Company: L.D. Drilling, Inc. phone: \_\_\_\_\_

Were: **Spot plugs through drill pipe w/ heavy mud between all plugs.**

1st plug @ 2455 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1400 feet " 100 " Mousehole: \_\_\_ sacks

3rd plug @ 300 feet " 40 "

4th plug @ 40 feet " wiper plug & 40 sx

Plugging Proposal Received by: David K. Wann

Plugging operations attended by agent? All[ ], Part[ ], None[ X ]


Completed: Hour: 8:00 pm Day: 22, Month: November, Year: 1995

Actual plugging report: Hole reported plugged as above.

Order 190 sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Elevation: 2996 GL, Anhydrite depth: 2460 - 2477 feet Anhy. plug: YES  
Dakota plug: YES Bottom hole plug in place: NO  
Plugged through drill pipe: YES  
Did NOT penetrate Arbuckle, cemented by Allied Cementing

I did  did not [  ] observe the plugging.

  
David K. Wann P.I.R.T. II  
(agent)

**INVOICED**  
DATE 2-6-96  
INV. NO. 44829

02-02-1996  
RECEIVED  
KANSAS CORP COMM  
1996 FEB -2 A 11:14