

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-109-20681-00-00  
Spot: SENESEW Sec/Twnshp/Rge: 36-13S-33W  
1800 feet from S Section Line, 2970 feet from E Section Line  
Lease/Unit Name: HILDEBRAND L Well Number: 1-36  
County: LOGAN Total Vertical Depth: 4604 feet

Operator License No.: 5030  
Operator Name: VESS OIL CORPORATION  
Address: 8100 E. 22ND N. BLDG. 300  
WICHITA, KS 67226

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 257  
Production: Size 0 feet: 0  
Liner: Size feet: 149.63

Well Type: DH UIC Docket No: Date/Time to Plug: 9/7/00 9:00:00 AM  
Plug Co. License No.: 6039 Plug Co. Name: L.D. DRILLING, INC.  
Proposal Rcvd. from: DORAN Company: L.D. DRILLING, INC. Phone: (316) 793-3051

Proposed Plugging Method: Ordered 190 sxs 60/40 pozmix with 6% gel - 1/4# Floseal per sack.  
One 8 5/8" wiper plug.  
Spot all plugs thru drill pipe with heavy drilling mud between all plugs.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: Plugging Operations Were Not Witnessed  
Date/Time Plugging Completed: 09/07/2000 11:30 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

No ar buckle cut.  
1st. Plug at 2363' w/25 sxs. - Middle of Anhy. (2352' - 2374').  
2nd. Plug at 1289' w/100 sxs. - Base Dkota (989' - 1289').  
3rd. Plug at 307' w/40 sxs. - Base Surface Pipe + 50'. 257" 8 5/8" set.  
4th. Plug at 40' w/10 sxs. - One 8 5/8" wiper plug.  
Plugged rathole with 15 sxs.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 25 2000  
09-25-2000  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks:

Plugged through:

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE

9/26/00

INV. NO.

2001060752