

6 030686

API NUMBER 15-109-20,284-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SESENE, SEC. 9, T. 13 S. R. 33 (W)2

2970 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5238

Lease Name GARVEY INC. Well # AS 1

Operator: PETROLEUM INC.

County LOGAN 151.78

Name & Address P.O. Box 1447

Well Total Depth 4670' feet

GREAT BEND KANSAS
67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1331'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor ROCKHOLD ENGINEERING License Number 5111

Address Box 698 GREAT BEND KANSAS 67530

Company to plug at: Hour: PM Day: 10 Month: 3 Year: 19 86

Plugging proposal received from DEACON

(company name) ROCKHOLD ENG. (phone) _____

were: 8 5/8 @ 1331 w/800sx. 5 1/2 @ 4669' w/225sx. PBTD 4621' PERF 4159'

ORDER SAND & COM. CMT. PULL PIPE ORDER 180sx. 60/40p02 6 1/2 GEL. 3 1/2 40sx

OR. 8 5/8 W.P. BJTITON CMT. CO. JOENEUMAN WATER TRUCKS.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 PM Day: 10 Month: 3 Year: 19 86

ACTUAL PLUGGING REPORT Dump SAND ON PBTD TO 4100' w/5sx. COM. CMT. ON SAND

w/BAILER - 5HOT @ 2500' & 2000' PULLED 2000'

MIX. & PUMP DOWN 8 5/8 3sx. HULLS 23sx. GEL. 100sx. CMT. MIX. + 1sx. HULLS

17sx. GEL. 8 5/8 W.P. 80 sx CMT. MIX. MAX. PSI 1500*

PLUG. COMPLETE

RECEIVED
STATE CORPORATION COMMISSION

MAR 24 1986
03-24 1986

CONSERVATION DIVISION
Wichita, Kansas

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

(MAR 25 1986) observe this plugging.

DATE _____

Signed Carl Goodrow
(TECHNICIAN)

INV. NO. 13110