

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-23360-00-00
Spot: S2SENEW Sec/Twnshp/Rge: 3-12S-13W
1280 feet from N Section Line, 2310 feet from W Section Line
Lease Name: ZWEIFEL TRUST A Well #: 1-3
County: RUSSELL Total Vertical Depth: 3800 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	428	0	225 SX CMT.
T1	2.375	3147		
PROD	4.5	3780	1500	225 SX CMT.

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/16/2011 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: GARY SHARP Company: TRANS PACIFIC OIL CORPORATIO Phone: (316) 262-3596

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls.
Sanded back and cut casing 1500' down.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/16/2011 1:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Pulled casing to 1200' - pumped 125 sxs cement with 400# hulls.
Pulled casing to 800' - pumped 40 sxs cement.
Pulled casing to 450' - pumped 50 sxs cement with 100# hulls.
Pulled casing to 250' - pumped 80 sxs cement - cement circulated into cellar.
POOH. Cellar stayed full.

Perfs:

Top	Bot	Thru	Comments
3112	3116		

Remarks: QUALITY WELL SERVICES-TICKET #5190.

Plugged through: CSG

District: 04

Signed Ray Dinkel
(TECHNICIAN) CM

RECEIVED
MAY 27 2011
KCC WICHITA

Form CP-2/3

MAY 19 2011