

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-25199-00-00  
Spot: SENWNWNE Sec/Twnshp/Rge: 21-18S-22W  
538 feet from N Section Line, 2114 feet from E Section Line  
Lease Name: LARRY STIEBEN Well #: 2-21  
County: NESS Total Vertical Depth: 4468 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: 3118 CUMMINGS RD PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	223		WITH 150 SX CMT
PROD	5.5	4464	2997	WITH 175 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/17/2011 11:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: SCOTT CORSAIR Company: AMERICAN WARRIOR Phone: (785) 398-2270

Proposed Plugging Method: SAND BOTTOM 50' ABOVE PERFS & 2 SX CMT. PLUG AT 1600' WITH 40 SX CMT. PLUG AT 800' WITH 60 SX CMT. PLUG AT 450' WITH 40 SX CMT. PLUG AT 240' WITH 40 SX CMT. 40 SX CMT AT 10'.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/17/2011 4:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SANDED BOTTOM TO 4250' & 2 SX CMT. 1ST PLUG AT 1600' WITH 40 SX CMT. 2ND PLUG AT 800' WITH 60 SX CMT. 3RD PLUG AT 450' WITH 40 SX CMT. 4TH PLUG AT 240' WITH 40 SX CMT. 5TH PLUG AT 40' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4320	4330		CHEROKEE

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

Signed Michael Maier  
(TECHNICIAN)

RECEIVED  
MAY 24 2011  
KCC DODGE CITY

RECEIVED  
MAY 31 2011  
Form CP-2/3  
KCC WICHITA

*Handwritten initials*