

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-23951-00-00  
Spot: SENWNESE Sec/Twnshp/Rge: 25-10S-20W  
2000 feet from S Section Line, 900 feet from E Section Line  
Lease Name: CHURCH OF GOD Well #: 1  
County: ROOKS Total Vertical Depth: 3800 feet

Operator License No.: 33306  
Op Name: BLAKE EXPLORATION, LLC  
Address: 201 S MAIN PO BOX 150  
BOGUE, KS 67625

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	224		

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/21/2011 12:00 PM  
Plug Co. License No.: 33493 Plug Co. Name: AMERICAN EAGLE DRILLING LLC  
Proposal Rcvd. from: BRAD Company: BLAKE EXPLORATION, LLC Phone: (785) 421-2921

Proposed Plugging Method: Ordered 230 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DARREL DIPMAN Witness Type: NONE  
Date/Time Plugging Completed: 05/21/2011 7:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

1st. Plug at 3732' w/25 sxs.  
2nd. Plug at 1640' w/25 sxs.  
3rd. Plug at 950' w/100 sxs.  
4th. Plug at 275' w/40 sxs.  
5th. Plug at 40' w/10 sxs.  
Rathole with 30 sxs.

Perfs:

Remarks: QUALITY OIL WELL CEMENTING.

Plugged through: DP

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

CM

RECEIVED  
MAY 31 2011  
Form CP-2/3

MAY 23 2011

KCC WICHITA