

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-00451-00-01
Spot: SWSWSE Sec/Twnshp/Rge: 14-22S-16W
334 feet from S Section Line, 2310 feet from E Section Line
Lease Name: SCHARTZ Well #: 1
County: PAWNEE Total Vertical Depth: 4122 feet

Operator License No.: 30104
Op Name: CAMBRON, PAUL L.
Address: 118 N PENN PO BOX 384
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3950		WITH 2 SX CMT
SURF	10.75	717		
PROD	4.5	4120	1857	WITH 125 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/19/2011 9:00 AM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: MARK HERSKOWITZ Company: CHEYENNE WELL SERVICE, INC. Phone: (785) 798-5050

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/19/2011 10:45 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3950' & PUT 2 SX CMT ON TOP OF CIBP. 1ST PLUG AT 1010' WITH 25 SX GEL & 70 SX CMT. 2ND PLUG AT 740' WITH 70 SX CMT. 3RD PLUG AT 400' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 40 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4008	4014		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

RECEIVED

MAY 31 2011

District: 01

Signed Stephen J Pfeifer
(TECHNICIAN)

KCC WICHITA

RECEIVED

MAY 24 2011

KCC DODGE CITY

RAW