

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-069-20345-00-00
Spot: SWSNWNE Sec/Twnshp/Rge: 17-28S-29W
1000 feet from N Section Line, 1710 feet from E Section Line
Lease Name: ROBERTSON Well #: 1-17(NE)
County: GRAY Total Vertical Depth: 5460 feet

Operator License No.: 5316
Op Name: FALCON EXPLORATION, INC.
Address: 125 N MARKET STE 1252
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1871		WITH 825 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/19/2011 6:30 AM
Plug Co. License No.: 5142 Plug Co. Name: STERLING DRILLING COMPANY
Proposal Rcvd. from: ALAN LOFTIS Company: STERLING DRILLING COMPANY Phone: (620) 672-9508

Proposed Plugging Method: 1ST PLUG AT 1890' WITH 50 SX CMT. 2ND PLUG AT 780' WITH 50 SX CMT. 3RD PLUG AT 390' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 05/19/2011 8:30 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

1ST PLUG AT 1890' WITH 50 SX CMT. 2ND PLUG AT 780' WITH 50 SX CMT. 3RD PLUG AT 390' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

RECEIVED
MAY 24 2011
KCC DODGE CITY

Signed Eric MacLaren
(TECHNICIAN)

KCC WICHITA

RECEIVED
MAY 31 2011

AMZ