

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-145-01067-00-00  
Spot: NWSWSW Sec/Twnshp/Rge: 4-23S-15W  
4343 feet from N Section Line, 354 feet from W Section Line  
Lease Name: CHESTER Well #: 2  
County: PAWNEE Total Vertical Depth: 3996 feet

Operator License No.: 3273  
Op Name: HERMAN L. LOEB, LLC  
Address: PO BOX 838  
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1000		
CIBP		3900		WITH 2 SX CMT,
CIBP		3958		
SURF	8.625	940		WITH 550 SX CMT
PROD	5.5	3989	0	WITH 150 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/26/2011 11:00 AM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: SHANE PELTON Company: HERMAN L. LOEB Phone: (719) 340-8987

Proposed Plugging Method: SET CIBP @ 3900' WITH 2 SX CMT. SET CIBP @ 1000'. PERFORATE 5 1/2" AT 970'. PUMP CMT DOWN 5 1/2" UNTIL CEMENT CIRCULATE UP 8 5/8" X 5 1/2" ANNULUS.

Plugging Proposal Received By: JERRY W. STAPLETON Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/26/2011 12:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 3900' WITH 2 SX CMT. SET CIBP @ 1000'. PERFORATE 5 1/2" @ 970'. PUMPED 200 SX 60/40 POZMIX 4% GEL FOLLOWED BY 60 SX COMMON CMT DOWN THE 5 1/2". CIRCULATED CMT TO SURFACE UP THE 8 5/8" X 5 1/2" ANNULUS.

Perfs:

Top	Bot	Thru	Comments
3959	3966		SIMPSON

Remarks: USED 60/40 POZMIX 4% GEL & COMMON CMT BY BASIC ENERGY.

Plugged through: CSG

RECEIVED  
MAY 31 2011

District: 01

RECEIVED  
MAY 27 2011

Signed

*Richard W. Lacey*  
(TECHNICIAN)

KCC WICHITA

KCC DODGE CITY

*Ball*