

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-057-20725-00-00
Spot: SESENWSE Sec/Twnshp/Rge: 18-25S-21W
1349 feet from S Section Line, 1393 feet from E Section Line
Lease Name: FROETSCHNER 'A' Well #: 1-18
County: FORD Total Vertical Depth: 5370 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	373		WITH 275 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/14/2011 1:00 PM
Plug Co. License No.: 5142 Plug Co. Name: STERLING DRILLING COMPANY
Proposal Rcvd. from: SHANE DONOVAN Company: STERLING DRILLING COMPANY Phone: (620) 672-9508

Proposed Plugging Method: 1ST PLUG AT 5312' WITH 50 SX CMT. 2ND PLUG AT 1380' WITH 50 SX CMT. 3RD PLUG AT 810' WITH 80 SX CMT. 4TH PLUG AT 400' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 05/14/2011 3:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

1ST PLUG AT 5312' WITH 50 SX CMT. 2ND PLUG AT 1380' WITH 50 SX CMT. 3RD PLUG AT 810' WITH 80 SX CMT. 4TH PLUG AT 400' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

RECEIVED
MAY 24 2011
KCC DODGE CITY

Signed Eric MacLaren
(TECHNICIAN)

KCC WICHITA

RECEIVED
MAY 31 2011

BMJ