

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-00614-00-01  
Spot: SENENE Sec/Twnshp/Rge: 14-21S-13W  
4356 feet from S Section Line, 310 feet from E Section Line  
Lease Name: DORAN Well #: 1  
County: STAFFORD Total Vertical Depth: 3554 feet

Operator License No.: 33978  
Op Name: WHITE HAWK OIL COMPANY, LLP  
Address: 15 E 5TH ST, STE 3200  
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3250		WITH 5 SX CMT
SURF	8.625	265		WITH 200 SX CMT
PROD	5.5	3546	563	CASING PARTED

Well Type: EOR UIC Docket No: E19576.1 Date/Time to Plug: 05/06/2011 12:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: CIBP @ 3250' & 5 SX CMT. PLUG AT 800' WITH 12 SX GEL & 50 SX CMT. PLUG AT 290' WITH 50 SX CMT. PLUG AT 60' WITH 15 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/06/2011 12:45 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

CIBP @ 3250' & 5 SX CMT. CASING PARTED AT 563'. LAID DOWN CASING. RUN TBG INTO PLUG. 1ST PLUG AT 800' WITH 15 SX GEL & 100 SX CMT. 2ND PLUG AT 290' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3406	3420		

Remarks: \*\*COMPLIANCE ISSUE: NOV MIT\*\*USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: TBG

District: 01

Signed

*Stephen J Pfeifer*  
(TECHNICIAN)

RECEIVED

MAY 31 2011

KCC WICHITA

RECEIVED

MAY 17 2011

KCC DODGE CITY