

8-17

6062221

API NUMBER 15-051-05296-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE _____, SEC. 27, T 11 S, R 17 W&E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5229

1320 feet from S section line

2130 ~~2310~~ feet from E section line

Operator: Phillips Petroleum Co.

Lease Name Baumer Well # B 43

Name & Address: Route #3 Box 20 A

County Ellis 118.33

Great Bend, Ks. 67530

Well Total Depth 3641 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1311

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050

Address Box 347 Chase, Ks. 67524

Company to plug at: Hour: 10:00AM Day: 17 Month: August Year: 19 90

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling Inc. (phone) 316-938-2943

were: Order 300 sks 60/40 poz 8% gel 5 sks hulls

*Change # 80-8621
Order # B842638*

RECEIVED
STATE CORPORATION COMMISSION
WICHITA, KANSAS

AUG 22 1990

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Gilbert G. Scheck (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:00PM Day: 17 Month: Aug. Year: 19 90

ACTUAL PLUGGING REPORT 8 5/8 set at 1311 w/650 sks. 5 1/2 set at 3639 w/200 sks.

Top perf at 3400. Plugged bottom w/sand and 5 sks cement to 3330. Shot pipe one time and recovered 2700. Pumped in 8 5/8 25 sks cement followed w/5 sks hulls in 275 sks cement w/ 500 psi.

Remarks: By Allied. Ran line to 1500.

(If additional description is necessary, use BACK of this form.)

INVOICED

(If) observe this plugging.

DATE: 8-28-90

Signed *Gilbert G. Scheck*
(TECHNICIAN)
Gilbert G. Scheck

E.S.D.

INV. NO. 28114

8-17