

9-11

6 062230

API NUMBER 15-051-05923-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE NW, SEC. 27, T 11 S, R 17 W/XX

3630 feet from S section line

3630 feet from E section line

Lease Name Baumer Well # B 16

County Ellis 111.93

Well Total Depth 3444 feet <sup>3555 feet AUB ECL</sup>

Conductor Pipe: Size 16 feet 38' w/45 sks

Surface Casing: Size 10 3/4 feet 1295

TECHNICIAN'S PLUGGING REPORT

Operator License # 5229

Operator: Phillips Petroleum Co.

Name & Address: Route Box 20 A

Great Bend, Ks. 67530

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050

Address Box 347 Chase, Ks. 67524

Company to plug at: Hour: 9:00 AM Day: 11 Month: Sept Year: 19 90

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling Inc. (phone) 316-938-2943

were: Order 300 sks 60/40 poz 8% gel 5 sks hulls.

Pay # B842638

Code # 80-8622

A.M. Wardell

Plugging Proposal Received by Gilbert G. Scheck (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 1:30 PM Day: 11 Month: Sept Year: 19 90

ACTUAL PLUGGING REPORT 10 3/4 set at 1295 w/500 sks. 7" set at

3542 w/175 sks. Open hole 13'. Plugged bottom w/sand and 7 sks cement to 3500. Shot

pipe three times and recovered 1936. Pumped in 10 3/4 50 sks cement followed w/5 sks

hulls in 250 sks cement w/ 500 psi.

Remarks: By Allied. Ran line to 1500. (If additional description is necessary, use BACK of this form.)

RCW  
SEP 19 1990

INVOICED

DATE 9-25-90

INV. NO. 29427  
9-11

Signed Gilbert G. Scheck (TECHNICIAN)

Gilbert G. Scheck E.A.S.