

6 062320

1-24

80-8621 98R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-051-05042-0000
E2NW SE, SEC. 27, T 11 S, R 17 W7E

1980 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5029

Lease Name Baumer B Well # 34

Operator: Phillips Petroleum Co.

County Ellis 116.54

Name & Address R.R. #3 Box 20 A

Well Total Depth 3586 feet

Great Bend, Ks. 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1326

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050

Address Box 347 Chase, Ks. 67524

Company to plug at: Hour: 8:00AM Day: 24 Month: Jan Year: 19 91

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling Inc. (phone) 316-938-2943

were: Order 300 sks of 60/40 poz 8% gel 5 sks hulls.

RECEIVED
STATE CORPORATION COMMISSION

FEB 13 1991

02-13-91

Plugging Proposal Received by Gilbert G. Scheck (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:30PMDay: 24 Month: Jan Year: 19 91

ACTUAL PLUGGING REPORT 8 5/8 set at 1326 w/525 sks. 4 1/2 set at 3565 w/175 sks.

Open hole 21'. Plugged bottom w/sand and 4 sks cement to 3500. Shot pipe three times and recovered 1120. Pumped in 8 5/8 25 sks cement followed w/5 sks hulls in 275 sks cement w/900 psi.

Remarks: Allied.

INVOICED

(If additional description is necessary, use BACK of this form.)

DATE 2-22-91

INV. NO. 30817

Signed Gilbert G. Scheck (TECHNICIAN) E. G. S.