

To: 6 031270
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-15-051-05931-0001 129
BC

NE SW NE, SEC. 27, T 11 S, R 17 W/E
3630 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5229
Operator: Phillips Pet. Co.
Name & Address: 710 East 10th
R. R. 3 Box 20A
Great Bend, Ks. 67530

Lease Name Baumer B Well # D-24
County Ellis 13016
Well Total Depth 4005 feet
Conductor Pipe: Size 16" feet 28'
10 3/4" set at 1225'
Surface Casing: Size 8 5/8 feet 1187

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well O&A _____

Other well as hereinafter indicated D-00,732

Plugging Contractor Express Well Service License Number 1545
Address Victoria, Ks.

Company to plug at: Hour: _____ PM Day: 15 Month: June Year: 19 89

Plugging proposal received from Phillips Kevin Snow
(company name) Phillips (phone) _____

were: 16" conductor set at 28' w/50 sks. 10 3/4" set at 1225' w/400 sks cwc.
8 5/8" set at 1187' cwc. 7" set at 3521' w/200 sks. O.H. 3800' - 4005'. 5 1/2" liner
set from 3800' to 3495' w/170 sks. Ordered 800 sks 65/35 poz 8% gel 500# hulls
Halliburton Cement Co.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:00 PM Day: 15 Month: June Year: 19 89

ACTUAL PLUGGING REPORT Ran tubing to 1600'. Pump 800 sks through tubing. Brought cement to
surface but wouldnt circulate. Laid down tubing to 600'. No circ. Laid
down tubing to 300'. No circ light blow, displaced cement at 100' holding.
Laid down tubing w.o.c. Squeeze 7" casing w/total of 1290sks to max psi 500#.
Close in 200 psi test 8 5/8" to 500 psi w/1 bbl cement. Test 10 3/4" to 500 psi
w/2 bbl cement. Plug complete.

Remarks: (If additional description, use BACK of this form.)

INVOICED
DATE 7-5-89
INV. NO. 25166

RECEIVED
JUN 29 1989
Signed Carl Goodrow
Wichita, Kansas (TECHNICIAN)