

8-17

6 062220

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-051-19401-0000

NE , SEC. 27, T 11 S, R 17 W/E

2970 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5229

Lease Name Baumer Well # B-27

Operator: Phillips Petroleum Co.

County Ellis 111.02

Name & Address Route 3, Box 20A

Well Total Depth 3416 feet

Great Bend, Ks. 67530

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 1145

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050

Address Box 347, Cahse, Ks. 67524

Company to plug at: Hour: 10:00 AM Day: 17 Month: August Year: 19 90

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling Inc.

Order 300 sks 60/40 poz 8% gel 5 sks hulls.

were:

*Change order 80-80 38
Pay order # 28426*

STATE CORPORATION COMMISSION

08-22-90
AUG 22 1990

CONSERVATION DIVISION
Wichita, Kansas

Well had been sq w/250 sks to surf.

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:00Am Day: 17 Month: August Year: 19 90

ACTUAL PLUGGING REPORT 10 3/4 set at 1145 w/440 sks. 7" set at 3403 w/175 sks.
Open hole 12'. Plugged bottom w/sand and 7 sks cement to 3350. Shot pipe two times

and recovered 0. PUmpeD in 10 3/4 50 sks cement followed w/5 sks hulls in 250 sks cement
w/400 psi.

Remarks: by Allied. Ran line 2500.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE: 8-28-90

Signed Gilbert G. Scheck
(TECHNICIAN)

INV. NO. 28113
8-17