

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-05928-00-00
Spot: CSWNENE Sec/Twnshp/Rge: 27-11S-17W
990 feet from N Section Line, 990 feet from E Section Line
Lease/Unit Name: BAUMER Well Number: 21
County: ELLIS Total Vertical Depth: 3429 feet

Operator License No.: 9312
Operator Name: EQUINOX OIL COMPANY
Address: 200 ARCO PLACE, STE 435
INDEPENDENCE, KS 67301

Conductor Pipe: Size 16 feet: 39
Surface Casing: Size 10.75 feet: 1175
Production: Size 7 feet: 3414
Liner: Size feet: 111, 44

Well Type: OIL UIC Docket No: Date/Time to Plug: 9/7/00 9:00:00 AM

Plug Co. License No.: Plug Co. Name:

Proposal Rcvd. from: DAVID J. STAHL Company: EQUINOX OIL COMPANY Phone: (785) 434-4638

Proposed 7" set at 3414' w/175 sxs. CIBP @ 3345'. Bad casing from 3045' to 3200'+.
Plugging Squeeze 1995 - 131' to 1041' w/125 sxs. 1898' to 1950' w/50 sxs.
Method: 1869' to 2350' w/250 sxs.
Ordered out 400 sxs Swift Multi Density Cement.

Plugging Proposal Received By: HUBERT DEINES

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 09/07/2000 11:00 AM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran 2 1/2" tubing to 3045'. Swift Service pumped 75 sxs w/400# hulls pulled to 2045'. Swift Services pumped 75 sxs w/300# hulls. Pulled to 1045' and pumped 75 sxs w/300# hulls. Cement circulated. PTOH. Squeezed 25 sxs. Max. P.S.I. 250#. S.I.P. 250#. Checked backside 600# cement in bradenhead.

RECEIVED
STATE CORPORATION COMMISSION

SEP 25 2000
09-25-00

Remarks: EMERGENCY PLUG ORDERS GIVEN WHILE RIG OVER HOLE.

CONSERVATION DIVISION
Wichita, Kansas

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

INVOICED

DATE 9/26/00
INV. NO. 2001060751

Form CP-2/3

SEP 19 2000

DEEP ROCK OIL CORP

#21 BAUMER

27-11-17W
SW NE NE

DEEP ROCK C

Contr.

ELLIS County

Contr.

E 1959 Comm. 9-20-37 Comp. 10-11-37 IP 3000 BOPD

E 2040 Com

Tops	Depth	Datum
ANH	1168	
ARB	3414	
TD	3429	

Casing
 10" 1175
 7" 3414
 300' OIH/2 hrs @ 3429

+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

Tops
ANH
ARB
TD

INDEPENDENT
WICHITA, KANSAS