

6 070609

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 051-22,594-00.00  
C SE NW, S 27 SEC. 27, T 13 S, R 20 WAE  
\_\_\_\_\_ feet from S section line  
\_\_\_\_\_ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6566

Lease Name Geibler Well # 2

Operator: Lehen Oil Corporation  
Name & Address: Box 21468  
Tulsa, Ok. 74124

County Ellis 124.90  
Well Total Depth 3843 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 200

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor B. J. Titan License Number \_\_\_\_\_

Address Box 69 Hays, Ks. 67601

Company to plug at: Hour: 9:30 AM Day: 13 Month: Oct Year: 19 87

Plugging proposal received from John Glenn

(company name) Kaiser Francis O Al Company (phone) 316-938-2457

were: 8 5/8" 200' S.P. cwc w/150 sks; 5 1/2" casing. Set at 3804' w/200 sks cement.  
4 1/2" liner at 3704' - 3826'. (Open hole) Junk in hole, casing bad. No pipe  
recovery. Proposal. Perf at 1525' and 780'; 250 sks 65/35/Pozmix 10% Gel  
5 sks Hulls. Spot cement with tubing and displace. Open annulus.

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:15PM Day: 13 Month: Oct Year: 19 87

ACTUAL PLUGGING REPORT Ordered 250 sks 65/35 Pozmix 10% Gel and 5 sks Hulls.

Perf. cate 780' and dt 1525' by L. K. Wireline.

With tubing spot and displace cement at 3550' w/75 sks cement; at 2050' w/150 sks cmt;  
Pumped 25 sks in annulus. Returned for another 75 sks cement. Pumped in annulus another  
25 sks cement; Max 600 Psig. Shut in 300 Psig. Squeezed 5 1/2" casing w/50 sks cement.  
550 Psig. Max shut in at 250 Psig.

Remarks: By B. J. Titan

(If additional description is necessary, use BACK of this report) CONSERVATION DIVISION  
Wichita, Kansas

INVOICED - 29-87  
did not observe this plugging.

DATE 11-20-87

INV. NO. 18936

Signed Marion J. Schmidt (TECHNICIAN)

Marion J. Schmidt