


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Ellis County, Sec. 27 Twp. 13S Rge. 20W (E) (W)

Location as "NE/CNW/SW" or footage from lines C N/2 SE SW  
Lease Owner Imperial Oil of Kansas, Inc.  
Lease Name Giebler "B" Well No. 2  
Office Address 780 Fourth National Bldg., Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well  
Date well completed January 22 19 53  
Application for plugging filed April 15 19 59  
Application for plugging approved April 17 19 59  
Plugging commenced April 20 19 59  
Plugging completed April 20 19 59  
Reason for abandonment of well or producing formation Commercial quantities of oil depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production April 20, 19 59  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3843 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	228'	228'
				5-5/8"	3837'	3837'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set No. 1 Plug at 550' with 20 sacks cement; Set No. 2 Plug at 225' with 20 sacks cement; Set No. 3 Plug at 40' with 15 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 3 1959

CONSERVATION DIVISION  
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Imperial Oil of Kansas, Inc.  
Address 780 Fourth National Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Raymond L. Bacon (employee of ~~Imperial Oil of Kansas, Inc.~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.

(Signature) By: Raymond L. Bacon V-P  
780 Fourth National Bldg., Wichita 2, Kansas  
(Address)

Subscribed and sworn to before me this 31st day of July, 19 59



Mona L. Latier  
Mona L. Latier, Notary Public.

PLUGGING  
FILE SEC. 27 T. 13 R. 20W  
BOOK PAGE 31 LINE 13

DRILLER'S LOG

RECORDED  
AUG 3 1959  
CONSERVATION DIVISION  
Wichita, Kansas

Imperial Drilling Company, Inc.  
903 Union National Bank Building  
Wichita 2, Kansas

Giebler "B" #2  
C.N. 1/2 SE SW 27-13S-20W  
Ellis County, Kansas

Total Depth: 3843' Elevation: 2240 R.B.  
Commenced: 1-7-53 Completed: 1-22-53 Production: 306 B.O.P.D.

Contractor: Imperial Drilling Company, Inc.  
903 Union National Bank Building  
Wichita, Kansas

15051-0539700-00

Casing Record: Set 228' of 8 5/8" surface pipe w/125 sacks cement.  
Set 5 1/2" oil string casing @ 3837' (6' off bottom).

Figures indicate bottom of formation:

Surface clay & sand	190'		<u>TOPS</u>
Sandy shale & shells	760'		
Shale & shells	1025'	Elevation	2240 R.B.
Sand	1250'	Topeka Limestone	3210 (- 970)
Shale & Shells	1542'	Heebner Shale	3465 (-1225)
Anhydrite	1585'	Toronto Limestone	3486 (-1246)
Shale & shells	2095'	Lans.-Kc. Limestone	3503 (-1263)
Lime & shale	3385'	Base Lans.-Kc. Limestone	3763 (-1523)
Lime	3838'	No Cong. present	
Arbuckle	3843'	Arbuckle Dolo.	3830 (-1590)
Total Depth(Rotary)	3843'	Rotary Total Depth	3843 (-1603)

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

IMPERIAL DRILLING COMPANY, INC.

By: Raymond J. Bacon  
Vice-President

Subscribed and sworn to before me this 27th day of January, 1953.

By: Raymond J. Little  
Notary Public

My commission Expires:

7-4-54

PLUGGING  
FILE SEC. 27 T. 13 R. 50W  
BOOK PAGE 31 LINE 13